

AD-A104 713

HORNER AND SHIFRIN INC ST LOUIS MO

F/6 13/13

NATIONAL DAM SAFETY PROGRAM. CONSERVATION CLUB LAKE DAM (MO 304-ETC(U)

DEC 79

DACW43-79-C-0047

NL

UNCLASSIFIED

1 OF 1
AD-A
104 713

END
DATE
FILMED
10-81
DTIC

AD A104713

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
	AD-A104713	
4. TITLE (and Subtitle) Phase I Dam Inspection Report National Dam Safety Program Conservation Club Lake Dam (MO 30414) Jefferson County, Missouri		5. TYPE OF REPORT & PERIOD COVERED Final Report
		6. PERFORMING ORG. REPORT NUMBER
7. AUTHOR(s) Horner & Shifrin, Inc.		8. CONTRACT OR GRANT NUMBER(s) DACW43-79-C-00471
9. PERFORMING ORGANIZATION NAME AND ADDRESS U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSED-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS 1235
11. CONTROLLING OFFICE NAME AND ADDRESS U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSED-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101		12. REPORT DATE December 1979
		13. NUMBER OF PAGES Approximately 60
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) National Dam Safety Program, Conservation Club Lake Dam (MO 30414), Mississippi - Kaskaskia - St. Louis Basin, Jefferson County, Missouri. Phase I Inspection		15. SECURITY CLASS. (of this report) UNCLASSIFIED
16. DISTRIBUTION STATEMENT Report. Approved for release; distribution unlimited.		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dam Safety, Lake, Dam Inspection, Private Dams		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report was prepared under the National Program of Inspection of Non-Federal Dams. This report assesses the general condition of the dam with respect to safety, based on available data and on visual inspection, to determine if the dam poses hazards to human life or property.		


DD FORM 1 JAN 73 1473

EDITION OF 1 NOV 65 IS OBSOLETE

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)



SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

INSTRUCTIONS FOR PREPARATION OF REPORT DOCUMENTATION PAGE

RESPONSIBILITY. The controlling DoD office will be responsible for completion of the Report Documentation Page, DD Form 1473, in all technical reports prepared by or for DoD organizations.

CLASSIFICATION. Since this Report Documentation Page, DD Form 1473, is used in preparing announcements, bibliographies, and data banks, it should be unclassified if possible. If a classification is required, identify the classified items on the page by the appropriate symbol.

COMPLETION GUIDE

General. Make Blocks 1, 4, 5, 6, 7, 11, 13, 15, and 16 agree with the corresponding information on the report cover. Leave Block 2 and 3 blank.

Block 1. Report Number. Enter the unique alphanumeric report number shown on the cover.

Block 2. Government Accession No. Leave blank. This space is for use by the Defense Documentation Center.

Block 3. Recipient's Catalog Number. Leave blank. This space is for the use of the report recipient to assist in future retrieval of the document.

Block 4. Title and Subtitle. Enter the title in all capital letters exactly as it appears on the publication. Titles should be unclassified whenever possible. Write out the English equivalent for Greek letters and mathematical symbols in the title (see "Abstracting Scientific and Technical Reports of Defense-sponsored RDT/E," AD-667 000). If the report has a subtitle, this subtitle should follow the main title, be separated by a comma or semicolon if appropriate, and be initially capitalized. If a publication has a title in a foreign language, translate the title into English and follow the English translation with the title in the original language. Make every effort to simplify the title before publication.

Block 5. Type of Report and Period Covered. Indicate here whether report is interim, final, etc., and, if applicable, inclusive dates of period covered, such as the life of a contract covered in a final contractor report.

Block 6. Performing Organization Report Number. Only numbers other than the official report number shown in Block 1, such as series numbers for in-house reports or a contractor/grantee number assigned by him, will be placed in this space. If no such numbers are used, leave this space blank.

Block 7. Author(s). Include corresponding information from the report cover. Give the name(s) of the author(s) in conventional order (for example, John R. Doe or, if author prefers, J. Robert Doe). In addition, list the affiliation of an author if it differs from that of the performing organization.

Block 8. Contract or Grant Number(s). For a contractor or grantee report, enter the complete contract or grant number(s) under which the work reported was accomplished. Leave blank in in-house reports.

Block 9. Performing Organization Name and Address. For in-house reports enter the name and address, including office symbol, of the performing activity. For contractor or grantee reports enter the name and address of the contractor or grantee who prepared the report and identify the appropriate corporate division, school, laboratory, etc., of the author. List city, state, and ZIP Code.

Block 10. Program Element, Project, Task Area, and Work Unit Numbers. Enter here the number code from the applicable Department of Defense form, such as the DD Form 1498, "Research and Technology Work Unit Summary" or the DD Form 1634, "Research and Development Planning Summary," which identifies the program element, project, task area, and work unit or equivalent under which the work was authorized.

Block 11. Controlling Office Name and Address. Enter the full, official name and address, including office symbol, of the controlling office. (Equates to funding/sponsoring agency. For definition see DoD Directive 5200.20, "Distribution Statements on Technical Documents.")

Block 12. Report Date. Enter here the day, month, and year or month and year as shown on the cover.

Block 13. Number of Pages. Enter the total number of pages.

Block 14. Monitoring Agency Name and Address (if different from Controlling Office). For use when the controlling or funding office does not directly administer a project, contract, or grant, but delegates the administrative responsibility to another organization.

Blocks 15 & 15a. Security Classification of the Report: Declassification/Downgrading Schedule of the Report. Enter in 15 the highest classification of the report. If appropriate, enter in 15a the declassification/downgrading schedule of the report, using the abbreviations for declassification/downgrading schedules listed in paragraph 4-207 of DoD 5200.1-R.

Block 16. Distribution Statement of the Report. Insert here the applicable distribution statement of the report from DoD Directive 5200.20, "Distribution Statements on Technical Documents."

Block 17. Distribution Statement (of the abstract entered in Block 20, if different from the distribution statement of the report). Insert here the applicable distribution statement of the abstract from DoD Directive 5200.20, "Distribution Statements on Technical Documents."

Block 18. Supplementary Notes. Enter information not included elsewhere but useful, such as: Prepared in cooperation with ... Translation of (or by) ... Presented at conference of ... To be published in ...

Block 19. Key Words. Select terms or short phrases that identify the principal subjects covered in the report, and are sufficiently specific and precise to be used as index entries for cataloging, conforming to standard terminology. The DoD "Thesaurus of Engineering and Scientific Terms" (TEST), AD-672 000, can be helpful.

Block 20. Abstract. The abstract should be a brief (not to exceed 200 words) factual summary of the most significant information contained in the report. If possible, the abstract of a classified report should be unclassified and the abstract to an unclassified report should consist of publicly-releasable information. If the report contains a significant bibliography or literature survey, mention it here. For information on preparing abstracts see "Abstracting Scientific and Technical Reports of Defense-Sponsored RDT&E," AD-667 000.



DEPARTMENT OF THE ARMY
ST. LOUIS DISTRICT, CORPS OF ENGINEERS
210 NORTH 12TH STREET
ST. LOUIS, MISSOURI 63101

IN REPLY REFER TO

SUBJECT: Conservation Club Lake Dam (Mo. 30414)

This report presents the results of field inspection and evaluation of the Conservation Club Lake Dam. It was prepared under the National Program of Inspection of Non-Federal Dams.

SUBMITTED BY:

SIGNED

Chief, Engineering Division

20 DEC 1979

Date

APPROVED BY:

SIGNED

Colonel, CE, District Engineer

20 DEC 1979

Date

For	<input checked="checked" type="checkbox"/>
181	<input type="checkbox"/>
MS	<input type="checkbox"/>
Approved	<input type="checkbox"/>
Application	<input type="checkbox"/>
Distribution/	
by Special Codes	
or	
Initial	

A

MISSISSIPPI - KASKASKIA - ST. LOUIS BASIN

CONSERVATION CLUB LAKE DAM

JEFFERSON COUNTY, MISSOURI

MO 30414

PHASE 1 INSPECTION REPORT NATIONAL DAM SAFETY PROGRAM



**United States Army
Corps of Engineers**

*... Serving the Army
... Serving the Nation*

St. Louis District

PREPARED BY: U. S. ARMY ENGINEER DISTRICT, ST. LOUIS

FOR: STATE OF MISSOURI

DECEMBER 1979

CONSERVATION CLUB LAKE DAM - MISSOURI INVENTORY NO. 30414

JEFFERSON COUNTY, MISSOURI

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

PREPARED BY:

HORNER & SHIFRIN, INC.
5200 OAKLAND AVENUE
ST. LOUIS, MISSOURI 63110

FOR:

U.S. ARMY ENGINEER DISTRICT, ST. LOUIS
CORPS OF ENGINEERS

DECEMBER 1979

HS-7925

PHASE I REPORT

NATIONAL DAM SAFETY PROGRAM

Name of Dam: Conservation Club Lake Dam
State Located: Missouri
County Located: Jefferson
Stream: Selma Branch
Date of Inspection: 26 July 1979

The Conservation Club Lake Dam, was visually inspected by engineering personnel of Horner & Shifrin, Inc., Consulting Engineers, St. Louis, Missouri. The purpose of this inspection was to assess the general condition of the dam with respect to safety and, based upon this inspection and available data, determine if the dam poses a hazard to human life or property.

The following summarizes the findings of the visual inspection and the results of certain hydrologic/hydraulic investigations performed under the direction of the inspection team. Based on the visual inspection, the present general condition of the dam is considered to be satisfactory; however, the following deficiencies were noticed during the inspection and are considered to have an adverse effect on the overall safety and future operation of the dam:

1. A dense cover of vegetation (brush, trees and tall grass) that may conceal animal burrows, exists on the downstream face of the dam. Tree roots and animal burrows can provide passageways for seepage that could develop into a piping condition that could lead to failure of the dam.

- page 1 -


2. A heavy growth of brush and small trees exist along the concrete lined invert section of the discharge channel.
This growth will restrict channel flow and reduce the discharge capacity of the spillway that could result in flooding of the channel and possible damage to the downstream face of the dam.
3. The downstream end of the concrete lined spillway channel invert is in a deteriorated condition, as is evidenced by extensive cracking and settlement of the concrete pavement, as well as severe erosion of the pavement subgrade. Continued erosion of the spillway channel could affect the stability of the channel banks.
4. Underseepage, as evidenced by wet, soft ground and ponded water, was observed in the vicinity of the downstream toe of slope junction with the right abutment. Uncontrolled seepage can develop into a piping condition that could lead to failure of the dam.


According to the criteria set forth in the recommended guidelines, the magnitude of the spillway design flood for the Conservation Club Lake Dam, which is classified as small in size and of high hazard potential, is specified to be a minimum of one-half the Probable Maximum Flood (PMF). Considering the fact that there are several commercial establishments (a Nickerson Farms Restaurant and two automotive service stations) are located just downstream of the dam, and that U.S. Highway 61 and Interstate Highway 55 also lie within the potential flood damage zone, it is recommended that the spillway for this dam be designed for the PMF. The Probable Maximum Flood (PMF) is the flood that may be expected from the most severe combination of critical meteorologic and hydrologic conditions that are reasonably possible in the region.

Results of a hydrologic/hydraulic analysis indicated that the existing spillway is inadequate to pass lake outflow resulting from a storm of PMF magnitude. The spillway is adequate to pass lake outflow resulting from the 1 percent chance (100-year frequency) flood and lake outflow corresponding to about 50 percent of the PMF lake inflow. According to the St. Louis District, Corps of Engineers, the length of the downstream damage zone, should failure of the dam occur, is estimated to be three and one-half miles. Accordingly, within the possible damage zone is U.S. Highway 61, Interstate Highway 55, three commercial buildings and four agricultural buildings.

A review of available data did not disclose that seepage or stability analyses of this dam was performed. This is considered a deficiency and should be rectified.

It is recommended that the Owner take the necessary action in the near future to correct or control the deficiencies and safety defects reported herein.


Karl L. Freese
P.E. Missouri E-16182


Albert B. Becker, Jr.
P.E. Missouri E-9168



OVERVIEW CONSERVATION CLUB LATE 1940

PHASE 1 INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

CONSERVATION CLUB LAKE DAM - ID. NO. 30414

TABLE OF CONTENTS

<u>Paragraph No.</u>	<u>Title</u>	<u>Page No.</u>
SECTION 1 - PROJECT INFORMATION		
1.1	General	1-1
1.2	Description of Project	1-1
1.3	Pertinent Data	1-3
SECTION 2 - ENGINEERING DATA		
2.1	Design	2-1
2.2	Construction	2-1
2.3	Operation	2-1
2.4	Evaluation	2-2
SECTION 3 - VISUAL INSPECTION		
3.1	Findings	3-1
3.2	Evaluation	3-3
SECTION 4 - OPERATIONAL PROCEDURES		
4.1	Procedures	4-1
4.2	Maintenance of Dam and Spillway	4-1
4.3	Maintenance of Outlet Operating Facilities	4-1
4.4	Description of Any Warning Systems in Effect	4-1
4.5	Evaluation	4-1

<u>Paragraph No.</u>	<u>Title</u>	<u>Page No.</u>
	SECTION 5 - HYDRAULIC/HYDROLOGIC	
5.1	Evaluation of Features	5-1
	SECTION 6 - STRUCTURAL STABILITY	
6.1	Evaluation of Structural Stability	6-1
	SECTION 7 - ASSESSMENT/REMEDIAL MEASURES	
7.1	Dam Assessment	7-1
7.2	Remedial Measures	7-2

LIST OF PLATES

<u>Plate No.</u>	<u>Title</u>
1	Regional Vicinity Map
2	Lake Watershed Map
3	Dam Plan and Profile
4	Dam Section & Spillway Profile
5	Lake Area-Storage Curves
6	Spillway Discharge Rating Curve

APPENDIX A - INSPECTION PHOTOGRAPHS

<u>Page No.</u>	<u>Title</u>
A-1 through A-5	Inspection Photographs

APPENDIX B - HYDROLOGIC AND HYDRAULIC ANALYSES

<u>Page No.</u>	<u>Title</u>
B-1, B-2	Hydrologic & Hydraulic Computations
B-3, B-4	Computer Input Data
B-5	Summary Dam Safety Analyses
B-6	PMF Hydrographs

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

CONSERVATION CLUB LAKE DAM - ID NO. 30414

SECTION 1 - PROJECT INFORMATION

1.1 GENERAL

a. Authority. National Dam Inspection Act, Public Law 92-367, dated 8 August 1972, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a program of safety inspection of dams throughout the United States. Pursuant to the above, the St. Louis District, Corps of Engineers, directed that a safety inspection of the Conservation Club Lake Dam be made.

b. Purpose of Inspection. The purpose of this visual inspection was to make an assessment of the general condition of the dam with respect to safety and, based upon available data and this inspection, determine if the dam poses a hazard to human life or property.

c. Evaluation Criteria. This evaluation was performed in accordance with the "Phase I" investigation procedures as prescribed in "Recommended Guidelines for Safety Inspection of Dams," Appendix D to "Report of the Chief of Engineers on the National Program of Dams," dated May 1975.

1.2 DESCRIPTION OF PROJECT

a. Description of Dam and Appurtenances. The Conservation Club Lake Dam is an earthfill type embankment rising approximately 30 feet above the original streambed. The embankment has an upstream slope (above the waterline) of 1v on 3h, a crest width of about 16 feet, and a downstream slope of 1v on 2.4h that flattens to 1v on 4.2h at a point about 18 feet

below the top of the dam. The length of the dam including the spillway section is approximately 590 feet. A plan and profile of the dam are shown on Plate 3 and a cross-section of the dam is shown on Plate 4. At normal pool elevation, the reservoir impounded by the dam, occupies approximately 19 acres. A 6-inch diameter pipe, with a control valve located in a concrete pit near the outlet end of the pipe, passes through the dam and serves as a lake drawdown facility.

The lake level is governed by a trapezoidal spillway section cut into bedrock and located at the left (west) abutment. The spillway crest is located approximately 100 feet upstream of the centerline of the dam. A concrete low-water bridge crosses the discharge channel immediately below the centerline of the dam. Four 6-inch diameter steel pipes are embedded in the bridge slab to enable low volume spillway releases to pass the bridge structure. Beginning approximately 50 feet below the centerline of the dam the invert of the spillway channel is paved with concrete. The paved section continues down the hillside of the adjacent watershed and joins the tributary of that watershed about 150 feet below the dam. A profile of the spillway channel is shown on Plate 4.

b. Location. The dam and lake are located on Selma Branch, approximately 6 miles southeast of Festus, Missouri, immediately west of Interstate Highway 55 and just south of U.S. Highway 61, as shown on the Regional Vicinity Map, Plate 1. The dam is located in Section 33, Township 40 North, Range 6 East, in Jefferson County.

c. Size Classification. The size classification based on the height of the dam and storage capacity, is categorized as small. (Per Table 1, Recommended Guidelines for Safety Inspection of Dams).

d. Hazard Classification. Conservation Club Lake Dam, according to the St. Louis District, Corps of Engineers, has a high hazard potential, meaning that if the dam should fail, there may be loss of life, serious damage to homes; or extensive damage to agricultural, industrial and commercial facilities, important public utilities, main highways, or

railroads. The estimated flood damage zone, should failure of the dam occur, as determined by the St. Louis District, extends three and one-half miles downstream of the dam. Within the possible damage zone is U. S. Highway 61, Interstate Highway 55, three commercial buildings, and four agricultural buildings.

e. Ownership. The lake and dam are owned by The Conservation Club. The address of the Conservation Club is: U.S. Highway 61 South, Festus, Missouri - 63028. Mr. Clifford Bins is the current secretary-treasurer of the club.

f. Purpose of Dam. The dam impounds water for recreational use by club members and their guests.

g. Design and Construction History. According to a representative of the Owner, the design, staking, and inspection of the dam while it was under construction was performed by a member of the Conservation Club, Mr. Charles LaRose and several of his associates. Mr. LaRose, now deceased, was an engineer, formerly employed by the Pittsburg Plate Glass Company. The dam was constructed in 1951, by the Bloomsdale Excavating Company of Bloomsdale, Missouri.

h. Normal Operational Procedure. The lake level is unregulated.

1.3 PERTINENT DATA

a. Drainage Area. The area tributary to the lake is essentially undeveloped and in a native state covered with timber. There are several dwellings and other buildings adjacent to the state road at the west side of the drainage area. The watershed above the dam amounts to approximately 166 acres. The watershed area is outlined on Plate 2.

b. Discharge at Damsite.

- (1) Estimated known maximum flood at damsite ... 30 cfs*
- (2) Spillway capacity ... 647 cfs (W.S. = Elev. 537.1)

*Based on an estimate of depth of flow as observed by a representative of the Owner.

c. Elevation (ft. above MSL). The following elevations were determined by survey and are based on a bench mark elevation (502.28) obtained from the Missouri State Highway Department and located at the southeast corner of the headwall for the culvert passing beneath Highway 61, approximately 35 feet north of the edge of the pavement and about 600 feet west of the centerline of Interstate Highway 55.

- (1) Top of dam ... 537.1 (min.)
- (2) Normal pool (spillway crest) ... 533.1
- (3) Streambed at centerline of dam ... 507₊
- (4) Maximum tailwater ... Unknown

d. Reservoir.

- (1) Length at normal pool (elevation 533.1) ... 1,500 ft.
- (2) Length at maximum pool (elevation 537.1) ... 1,900 ft.

e. Storage.

- (1) Normal pool ... 135 ac. ft.
- (2) Top of dam (incremental) ... 85 ac. ft.

f. Reservoir Area.

- (1) Normal pool ... 19 acres
- (2) Top of dam ... 24 acres

g. Dam.

- (1) Type ... Earthfill, homogeneous*
- (2) Length ... 590 ft.
- (3) Height ... 30₊ ft. (above original streambed)
- (4) Top width ... 16 ft.
- (5) Side slopes
 - A. Upstream ... 1v on 3h
 - B. Downstream ... 1v on 2.4h (above Elev. 519.3)
1v on 4.2h (below Elev. 519.3)

*Per a representative of the Owner.

- (6) Cutoff ... Clay core*
- (7) Slope protection
 - a. Upstream ... Pre-cast concrete slab, stone at spillway
 - b. Downstream ... Grass

h. Spillway.

- (1) Type ... Uncontrolled, rock ledge, trapezoidal section
- (2) Crest elevation ... 533.1
- (3) Approach channel ... Lake
- (4) Exit channel ... Earth cut, trapezoidal section partially paved invert

i. Lake Drawdown Facility.

- (1) Size ... 6-Inch steel pipe
- (2) Control ... Valve (at outlet end)
- (3) Elevation (Ft. above MSL) ... 511.9 (outlet)

j. Regulating Outlets. With the exception of the lake drawdown pipe, there are no outlets at this dam where lake outflow can be regulated.

*Per a representative of the Owner.

SECTION 2 - ENGINEERING DATA

2.1 DESIGN

Mr. Marvin LaRose, a member of the Conservation Club Board of Directors at the time of construction of the dam reported that the design, staking and inspection of the dam while it was under construction was performed by Mr. Charles LaRose and several of his associates. Mr. Charles LaRose, a distant cousin of Marvin and an engineer formerly with the Pittsburgh Plate Glass Company, is deceased. Attempts to obtain any design data were unsuccessful.

2.2 CONSTRUCTION

According to a representative of the Owner, any records maintained during construction of the dam are no longer available. Mr. Marvin Drury, a representative of the Bloomsdale Excavating Company, builders of the dam, reported that a 15-foot wide core trench was excavated along the centerline of the dam. When the trench reached a depth of about 5 feet, a sand seam was encountered and the trench was extended to about 20 feet in depth in order to reach sound rock. The material used to backfill the trench and construct the embankment, a silty, sandy clay, was obtained from the area to be occupied by the lake. Compaction was obtained by the equipment used to haul the fill.

Mr. Marvin LaRose also reported that due to the presence of a rock ledge at the planned spillway location, the spillway crest was raised about one foot higher than originally intended.

2.3 OPERATION

The lake level is governed by an uncontrolled spillway cut to rock at the left abutment. A representative of the Owner reported that the dam

has never been overtopped and that the highest lake level observed occurred this past spring (1979) when the lake reached a level estimated to be about one foot higher than the spillway crest.

2.4 EVALUATION

a. Availability. Engineering data for assessing the design of the dam and spillway were unavailable.

b. Adequacy. No data available. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency. These seepage and stability analyses should be performed for appropriate loading conditions (including earthquake loads) and made a matter of record.

SECTION 3 - VISUAL INSPECTION

3.1 FINDINGS

a. General. A visual inspection of the Conservation Club Lake Dam was made by Horner & Shifrin engineering personnel, K.L. Freese, Civil Engineer and Hydrologist, and A.B. Becker, Jr., Civil and Soils Engineer, on 26 July 1979. An examination of the dam site was also made by an engineering geologist, Jerry D. Higgins, a consultant retained by Horner & Shifrin for the purpose of assessing the area geology. Also examined at the time of the inspection, was the area below the dam within the potential flood damage zone. Photographs of the dam taken at the time of the inspection are included on Pages A-1 through A-5 of Appendix A.

b. Area Geology. The dam site is located on the northeastern flank of the Ozark Uplift where the bedrock strata are composed primarily of eastward-dipping limestones and sandstones that slope into the Illinois Basin.

The bedrock underlying the Conservation Club Lake and dam site is the St. Peter Sandstone, upon which a shallow covering of sandy, clay residual soil has developed. The St. Peter is characterized as a white, fine-to-medium-grained pure quartz sandstone. It is generally massively bedded and, although it is loosely cemented, exposed rock surfaces usually have been case hardened by the weathering process. Several outcrops of St. Peter sandstone occur around the lake, particularly along the eastern side and on the adjacent hillsides.

The abutments are moderately sloping, composed of bedrock and a thin veneer of unconsolidated materials. Several wet-weather springs were reported to be located in the tributary stream valleys, but no sign of flowing water was observed at the time of the inspection.

No adverse geologic conditions were observed that would be considered conducive to severe reservoir leakage or dam instability.

c. Dam. The visible portions of the upstream and downstream faces of the dam (see Photos 1 & 2) appeared to be in sound condition, although the downstream face of the dam has a dense cover of brush, small trees and weeds. In addition, several trees, up to 6-inches in diameter, exist on the downstream embankment near the left abutment. No animal burrows were noticed, but due to the dense cover of vegetation on the downstream face, it could not be concluded that none exist. Both the crest and upstream face of the dam have a well maintained cover of grass. The upstream face of the dam is protected from erosion by wave action by sections of pre-cast concrete panels approximately 1 inch in thickness, placed on a bed of 1-inch crushed stone (see Photo 9). No cracking of the surface or misalignment of the crest of the dam was evident.

Seepage, indicated by standing water, was noticed at the base of the dam near the right abutment. Since flow was indistinguishable an estimate of the seepage quantity could not be made.

A fabricated steel foot bridge crosses the spillway channel (see Photo 3) immediately downstream from the crest. The bridge supports rest on concrete pads but are not attached thereto. The spillway channel between the lake and the low-water bridge (see Photo 4) with the exception of the foot bridge is clear and well maintained. Stone riprap serves to protect the right bank or dam side of the spillway channel in the vicinity of the dam. The concrete low water bridge (see Photo 5) appeared to be in sound condition, although some cracking and spalling of the surface was apparent. A section of the outlet channel, beginning about 50 feet north of the dam centerline and extending to the valley floor, is paved across the invert with concrete (see Photo 6). With the exception of the section at the downstream end of the channel, (see Photo 7) which is undercut by erosion, broken and displaced, the concrete paved invert is in fair condition with only minor cracking and spalling due to weathering. Small trees and dense brush (see Photo 6) were also noticed adjacent to most of the paved spillway channel section.

The 3.5-foot by 4.5-foot concrete valve box with steel plate cover at the drawdown pipe outlet (see Photo 8) appeared to be in sound condition. However, the steel cover to the valve box could not be removed to examine the valve.

d. Downstream Channel. A restaurant and parking lot has been constructed in the area adjacent to the downstream channel (see Photo 10) immediately below the dam and south of Highway 61. Drainage from the watershed above the restaurant could be seen disappearing into a low area at the edge of the parking lot at the rear of the restaurant, however, an intake headwall or inlet structure was not noticed. Highway 61 is located just north of the parking lot, about 600 feet below the dam. A 6-foot by 6-foot box culvert carries the stream flow beneath the highway. At the upstream end of the box culvert on the south side of the highway, a concrete inlet structure has been constructed to collect drainage from the parking lot and part of the area south of the highway. Two 15-inch pipes and a 30-inch pipe are connected to the inlet structure. It is presumed that the 30-inch pipe carries the entire flow from the upper watershed, including the lake, beneath the restaurant parking lot.

Beyond Highway 61, the channel is unimproved and extends for approximately three miles before joining the Mississippi River. At a distance of about 2,000 feet, a 7-foot high by 8-foot wide box culvert allows the stream to pass beneath Interstate Highway 55. Between Interstate 55 and the Mississippi River, the stream winds through Selma Farms, a property owned by the Missouri Pacific Railroad Company. Immediately before joining the Mississippi River the stream passes under railroad tracks belonging to the St. Louis-San Francisco Railway Company.

e. Reservoir. The area adjacent to the lake is for the most part in a natural state and wooded. There did not appear to be significant sedimentation within the reservoir.

3.2 EVALUATION

The deficiencies observed during this inspection and noted herein, are not considered significant to warrant immediate remedial action.

Since it appears that spillway outflow must pass through a 30-inch pipe in order to continue downstream of Highway 61, it is likely that flooding of the area immediately below the dam will occur due to lack of capacity of this pipe as a result of runoff from storms of less than 1/2 the probable maximum flood magnitude.

SECTION 4 - OPERATIONAL PROCEDURES

4.1 PROCEDURES

The spillway is uncontrolled. The water surface level is governed by precipitation runoff, evaporation, seepage, and the capacity of the uncontrolled spillway.

4.2 MAINTENANCE OF DAM AND SPILLWAY

The upstream slope and crest of the dam are well maintained as is the area about the lake. Vegetation on the downstream slope is unattended. Judging from the deteriorated condition of the downstream end of the spillway channel as well as the dense growth of brush adjacent to the lower, paved section of the spillway channel, it is evident that these areas have received little attention. Also it would appear that there is a lack of concern for seepage problems or drainage of the affected areas. It was reported that muskrats are removed from the dam area during the winter time.

4.3 MAINTENANCE OF OUTLET OPERATING FACILITIES

With the exception of the lake drawdown pipe, no outlet operating facilities exist at this dam.

4.4 DESCRIPTION OF ANY WARNING SYSTEMS IN EFFECT

The inspection did not reveal the existence of a dam warning system.

4.5 EVALUATION

Inadequate or lack of maintenance is considered detrimental to the safety of a dam. It is recommended that maintenance of the dam and spillway be undertaken on a regular basis and that records be kept of all maintenance work performed.

SECTION 5 - HYDEAULIC/HYDROLOGIC

5.1 EVALUATION OF FEATURES

a. Design Data. Design data are not available. Procedures and data for determining the probable maximum flood, the 100-year frequency flood, and the discharge rating curve for flow passing the spillway and dam crest are presented on pages B-1 and B-2 of the Appendix.

b. Experience Data. The drainage area and lake surface area were developed from the USGS Selma, Illinois-Missouri, Quadrangle Map. The proportions and dimensions of the spillway and dam were developed from surveys made during the inspection.

c. Visual Observations.

- (1) The spillway, a trapezodial section founded on rock, has a bottom width of approximately 32 feet at the crest.
- (2) The spillway is located adjacent to the embankment at the left (west) abutment.
- (3) An 80-foot long, nearly level, grass-covered channel conducts flow through the spillway section. A low-water bridge, consisting of a 12-inch concrete slab with four 6-inch cast-iron pipes cast in the concrete to allow minor spillway flow to pass the bridge and continue downstream, is directly in line with the axis of the dam. Beginning at a point about 32 feet downstream of the low-water bridge the channel invert is paved with concrete. This paved invert section conducts flow away from the dam by following a course that leads to the valley immediately west of the dam watershed. The paved invert section is in a deteriorated condition throughout the reach that carries flow across the hillside.

(4) An emergency spillway is not provided.

(5) A 6-inch cast-iron pipe with a control valve near the outlet end is provided to dewater the lake. The pipe is exposed at the toe of the embankment where a concrete structure encloses the control valve.

(6) It appears that lake outflow must pass through a 30-inch diameter pipe in order to reach the downstream channel north of Highway 61, approximately 600 feet below the dam. The upstream end of this pipe could not be located at the time of the inspection.

d. Overtopping Potential. The spillway is inadequate to pass the probable maximum flood without overtopping the dam. The spillway is capable of passing the 1 percent chance (100-year frequency) flood without overtopping the dam. The results of a dam overtopping analysis are as follows:

<u>Ratio of PMF</u>	<u>Q-Peak Outflow(cfs)</u>	<u>Max. Lake W.S. Elev.</u>	<u>Max. Depth (Ft.)</u>	<u>Duration of</u>
			<u>of Flow Over Dam</u>	<u>Overtopping</u>
			<u>(Elev. 537.1)</u>	<u>Of Dam</u>
				<u>(Hours)</u>
0.50	647	537.1	0.0	0.2
1.00	3,025	538.3	1.2	1.8
100-Yr.Flood	50	534.3	0.0	0.0

Elevation 537.1 was found to be the lowest point in the dam crest. The flow safely passing the spillway just prior to overtopping was determined to be about 647 cfs, which is equivalent to about 50 percent of the probable maximum flood inflow. This outflow is greater than the outflow for the 1-percent chance (100-year frequency) flood. During peak

flow of the probable maximum flood, the greatest depth of flow over the dam would be approximately 1.2 feet and the overflow will extend about 550 feet along the crest of the dam; nearly the entire crest.

e. Evaluation. It is known that the type of material (silty, sandy clay) used to construct the dam can under certain conditions, such as high velocity flow, be very erodible. The downstream end of the spillway channel is extensively eroded due, primarily, to spillway flows at high velocities. For the PMF condition where the depth of flow overtopping the dam (1.2 feet maximum) and the duration of flow over the dam (1.8 hours) are appreciable, failure of the dam due to overtopping is a possibility.

SECTION 6 - STRUCTURAL STABILITY

6.1 EVALUATION OF STRUCTURAL STABILITY

a. Visual Observations. Visual observations which adversely affect the structural stability of the dam are discussed in Section 3, paragraph 3.1c.

b. Design and Construction Data. No design or construction data relating to the structural stability of the dam are known to exist. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency. These seepage and stability analyses should be performed for appropriate loading conditions (including earthquake loads) and made a matter of record.

c. Operating Records. With the exception of the valve on the lake drawdown pipe, no appurtenant structures or facilities requiring operation exist at this dam. According to the Owner, no records are kept of the lake level, spillway discharge, dam settlement, or seepage.

d. Post Construction Changes. According to the Owner, no post construction changes have been made which would affect the structural stability of the dam.

e. Seismic Stability. Since the dam is located within a Zone II seismic probability area, an earthquake of the magnitude predicted is not expected to produce a hazardous condition to the dam, provided that static stability conditions are satisfactory and conventional safety margins exist.

SECTION 7 - ASSESSMENT/REMEDIAL MEASURES

7.1 DAM ASSESSMENT

a. Safety. A hydraulic analysis indicates the spillway is capable of passing lake outflow of about 647 cfs without the level of the lake exceeding the low point in the top of the dam. A hydrologic analysis of the lake watershed area, as discussed in Section 5, paragraph 5.1d, indicates that for storm runoff of probable maximum flood magnitude, the lake outflow would be on the order of 3,025 cfs; for one-half the PMF the lake outflow would be approximately 647 cfs; and that for the 1 percent chance (100-year frequency) flood, the lake outflow would be about 50 cfs.

Several items were noticed during the inspection that could adversely affect the safety of the dam. These items include seepage, brush, and trees on the downstream face of the dam, and erosion of the steep, downstream section of the spillway outlet channel.

Stability and seepage analyses of the dam were not available for review and therefore no judgment could be made with respect to the structural stability of the dam.

b. Adequacy of Information. Due to lack of design and construction data, the assessments reported herein were based on external conditions as determined during the visual inspection. The assessment of the hydrology of the watershed and capacity of the spillway were based on a hydrologic/hydraulic study as indicated in Section 5. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency.

c. Urgency. The items concerning the safety of the dam noted in Paragraph 7.1a and the remedial measures recommended in paragraph 7.2 should be accomplished in the near future. The item regarding the spillway capacity recommended in paragraph 7-2a should be pursued on a high priority basis.

d. Necessity for Phase II. Based on the results of the Phase I Inspection, a Phase II investigation is not recommended.

e. Seismic Stability. Since the dam is located within a Zone II seismic probability area, an earthquake of the magnitude predicted is not expected to produce a hazardous condition to the dam, provided that static stability conditions are satisfactory and conventional safety margins exist.

7.2 REMEDIAL MEASURES

a. Recommendations. The following actions are recommended:



- (1) Based upon criteria set forth in the recommended guidelines, alterations to the design of the dam should be made in order to pass lake outflow resulting from a storm of probable maximum flood magnitude.
- (2) Obtain the necessary soil data and perform dam stability and seepage analyses in order to determine the structural stability of the dam for all operational conditions. Seepage and stability analyses should be performed by a qualified professional engineer experienced in the design and construction of dams.

b. Operations and Maintenance (O & M) Procedures. The following O & M Procedures are recommended:

- (1) Remove the trees and brush that may conceal animal burrows from the downstream face of the dam. Tree roots and animal burrows provide a passageway for seepage that can lead to a piping condition and subsequent failure of the dam. The existing turf cover should be restored if destroyed or missing. Maintain the

turf cover on the slopes at a height that will not hinder inspection of the slope or provide cover for burrowing animals. The removal of trees should be performed under the direction of an engineer experienced in the design and construction of earth dams.

- (2) Remove the brush and trees adjacent to the spillway outlet channel that restrict flow in the channel and reduce the discharge capacity of the section. Loss of spillway outlet capacity can result in flooding of the downstream face of the dam and conditions that could impair the stability of the embankment.
- (3) Restore the eroded areas of the spillway channel and provide some form of protection to prevent future erosion of the channel by spillway flow.
- (4) Provide some means of preventing piping (progressive internal erosion) due to seepage at the right abutment area. A piping condition could result in failure of the dam.
- (5) Provide maintenance of all areas of the dam including the lake drawdown control valve and spillway on a regularly scheduled basis in order to insure features of being in satisfactory operational condition.
- (6) A detailed inspection of the dam should be instituted on a regular basis by an engineer experienced in the design and construction of dams. It is also recommended, for future reference, that records be kept of all inspections made and remedial measures taken.




LOCATION MAP



**JEFFERSON
COUNTY**

CONSERVATION CLUB LAKE




REGIONAL VICINITY MAP






6
PHOTO LOCATION & KEY
(SEE APPENDIX A)




PLAN OF DAM
 SCALE: 1" = 50'



DAM CREST
 SCALE: 1" = 5' V., 1" = 50' H.


CONSERVATION CLUB LAKE
 DAM PLAN & PROFILE
 Horner & Shifrin, Inc. Sept. 1979

12




DAM CROSS SECTION STA. 2+50

SCALES: 1" = 10' V., 1" = 20' H.




PROFILE SPILLWAY

SCALES: 1" = 10' V., 1" = 20' H.





A. 2+50

H.



**CONSERVATION CLUB LAKE
DAM CROSS-SECTION &
SPILLWAY PROFILE**
Horner & Shifrin, Inc. Sept. 1979





CONSERVATION CLUB LAKE
AREA-STORAGE CURVES


Horner & Shifrin, Inc.


Sept. 1979

1500 VOLUME (ACRE-FT) 2000
60, AREA (ACRES) 80

2500
100

PLATE 5





CONSERVATION CLUB LAKE
DISCHARGE RATING CURVE

Horner & Shifrin, Inc.

Sept. 1979

1500
DISCHARGE (cfs)

2000


2500

PLATE 6

APPENDIX A

INSPECTION PHOTOGRAPHS


INSPECTION PHOTOGRAPHS - CONSERVATION CLUB LAKE DAM




NO. 1: UPSTREAM FACE OF DAM



NO. 2: DOWNSTREAM FACE OF DAM



NO. 3: SPILLWAY APPROACH CHANNEL AND CREST



NO. 4: SPILLWAY OUTLET CHANNEL



NO. 5: LOW-WATER BRIDGE AT SPILLWAY CHANNEL



NO. 6: PAVED SPILLWAY CHANNEL INVERT



NO. 7: DETERIORATED PAVED SPILLWAY CHANNEL INVERT



NO. 8: VALVE PIT AND 6-INCH DRAWDOWN PIPE OUTLET



NO. 9: CONCRETE SLOPE PROTECTION



NO. 10: DOWNSTREAM CHANNEL NEAR DAM

APPENDIX B

HYDROLOGIC AND HYDRAULIC ANALYSES

HYDROLOGIC AND HYDRAULIC COMPUTATIONS

1. The HEC-1 Dam Safety Version (July 1978, Modified 26 February 1979) program was used to develop inflow and outflow hydrographs and dam overtopping analyses, with hydrologic inputs as follows:

a. Probable maximum precipitation (200 sq. miles, 24-hour value equals 25.5 inches) from Hydrometeorological Report No. 33. The precipitation data used in the analysis of the 1 percent (100-year flood) was provided by the St. Louis District, Corps of Engineers.

b. Drainage area = 0.26 square miles = 166 acres.

c. SCS parameters:

Soil Group B = 100 percent

Soil Type CN = 61 (AMC II, 100-yr. flood condition)

= 78 (AMC III, PMF condition)

Lag time = $0.60 T_c$ (SCS Method) = 0.068 hours

Time of Concentration (T_c) = $\left(\frac{11.9L^3}{H}\right)^{0.385}$ = 0.113 hours

Where: T_c = Travel time of water from hydraulically most distant point to point of interest, hours.

L = Length of longest watercourse, miles.

H = Elevation difference, feet.

2. The spillway section consists of a broad-crested, trapezoidal section for which conventional weir formulas do not apply.

Spillway release rates for this section were determined as follows:

a. Spillway crest section properties (area, "a" and top width, "t") were computed for various depths, "d".

b. It was assumed that flow over the spillway crest would occur at critical depth. Flow at critical depth (Q_c) was computed as: $Q_c = \left(\frac{d^3 g}{t}\right)^{0.5}$ for the various depth, "d". Corresponding velocities (v_c) and velocity heads (H_{vc}) were determined using conventional formulas.

c. Static lake levels corresponding to the various values passing over the spillway were computed as critical depths plus critical velocity heads ($d_c + H_{vc}$), and the relationship between lake level and spillway discharge was thus obtained. The procedure neglects the minor insignificant friction losses across the length of the spillway.

3. The profile of the dam crest is irregular and flow over the dam crest cannot be determined by conventional weir formulas. Flow quantities overtopping the dam crest were computed as described in the preceding paragraph and corresponding flow over the dam and spillways for given elevations were added to obtain the combined outflow rating curve for the dam and spillway.

4. A listing of the HEC-1 (Dam Safety Version) input data for routing the probable maximum flood and the 1 percent chance (100-year frequency) flood is shown on Pages B-3 and B-4 of the Appendix. A copy of the computer output table entitled "Summary of Dam Safety Analysis" is presented on Page B-5 and the inflow and outflow hydrographs for the probable maximum flood are shown on Page B-6 of the Appendix. Area-storage curves for the reservoir are presented on Plate 5 and the spillway discharge rating curve is shown on Plate 6.

ANALYSIS OF DAM OVERTOPPING USING RATIOS OF PMF
HYDROLOGIC-HYDRAULIC ANALYSIS OF SAFETY OF CONSER- CLUB LAKE DAM
RATIOS OF PMF ROUTED THROUGH RESERVOIR

STATION	PMF ROUTED	RESERVOIR ROUTING BY MODIFIED PULS	SAFETY OF CONSER	CLUB LAKE DAM
A1	285			0
A2	1			
A3	.43			
B1	1			
J1	.51	1.0		
K1	0		1	
M1	0			
P1	0			
T1	0			
W2	0			
X1	0			
X2	0			
X3	0			
X4	0			
X5	0			
X6	0			
X7	0			
X8	0			
X9	0			
X10	0			
X11	0			
X12	0			
X13	0			
X14	0			
X15	0			
X16	0			
X17	0			
X18	0			
X19	0			
X20	0			
X21	0			
X22	0			
X23	0			
X24	0			
X25	0			
X26	0			
X27	0			
X28	0			
X29	0			
X30	0			
X31	0			
X32	0			
X33	0			
X34	0			
X35	0			
X36	0			
X37	0			
X38	0			
X39	0			
X40	0			
X41	0			
X42	0			
X43	0			
X44	0			
X45	0			
X46	0			
X47	0			
X48	0			
X49	0			
X50	0			
X51	0			
X52	0			
X53	0			
X54	0			
X55	0			
X56	0			
X57	0			
X58	0			
X59	0			
X60	0			
X61	0			
X62	0			
X63	0			
X64	0			
X65	0			
X66	0			
X67	0			
X68	0			
X69	0			
X70	0			
X71	0			
X72	0			
X73	0			
X74	0			
X75	0			
X76	0			
X77	0			
X78	0			
X79	0			
X80	0			
X81	0			
X82	0			
X83	0			
X84	0			
X85	0			
X86	0			
X87	0			
X88	0			
X89	0			
X90	0			
X91	0			
X92	0			
X93	0			
X94	0			
X95	0			
X96	0			
X97	0			
X98	0			
X99	0			
X100	0			

SUMMARY OF DAM SAFETY ANALYSIS

RATIOS OF PMF				TOP OF DAM			
ELEVATION		INITIAL VALUE		SPILLWAY CREST		MAX CFS DAM	
STORAGE		533.09		533.10		537.10	
OUTFLOW		135.		335.		220.	
		0.		0.		647.	
RATIO OF PMF	MAXIMUM RESERVOIR W.S. ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FY	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
	537.09	0.00	219.	642.	0.00	15.83	0.00
	537.14	.04	221.	661.	.17	15.83	0.00
	537.19	.09	222.	681.	.33	15.83	0.00
1.00	538.30	1.20	248.	3025.	1.75	15.67	0.00

SUMMARY OF DAM SAFETY ANALYSIS

100-YR. FLOOD				TOP OF DAM			
ELEVATION		INITIAL VALUE		SPILLWAY CREST		MAX CFS DAM	
STORAGE		533.09		533.10		537.10	
OUTFLOW		135.		335.		220.	
		0.		0.		647.	
RATIO OF PMF	MAXIMUM RESERVOIR W.S. ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FY	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
	534.31	0.00	159.	50.	0.00	16.33	0.00

CONSERVATION CLUB LAKE PMF INFLOW & OUTFLOW HYDROGRAPHS

Horner & Shifrin, Inc.

Dec. 1979

